

SURVEY & REMONUMENTATION

MAY 05 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 2 PAGE 58
STATE OF MICHIGAN
BENZIE COUNTY
RECORDED

For corners in

<u>Benzie</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>25N</u> R <u>15W</u>	<u>H-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

1/22/1997 1:56:31 PM
MICHELLE R. GRAY
REGISTER OF DEEDS
PAGES _____

Register of Deeds Stamp & File Number

I, John B. Smendzuik, in a field survey on 6/4 and 9/25, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

H-11: G.L.O. set post and witnesses - 10" Sugar S3°W 57.42' and 8" Beech N18° 22.44'. Certificate of Survey by Bruce Jenema, dated August of 1993, shows 1/2" iron set M.O.L.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-11: Found 1/2" iron per Jenema survey.

Ratified by Peer Group
In accordance with P.A. 345
Chairman [Signature]
Date 12/27/95

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-11: Set 3" diameter Benzie County Remonumentation Program concrete monument in monument box at Jenema position.

- Power pole N78°E 113.58'
- Fiber optics phone riser S55°W 48.80'
- 1/2" x 18" iron w/cap 30895 N9°W 30.90' - witness irons only
- 1/2" x 18" iron w/cap 30895 S2°W 82.12 - witness irons only

Signed by

[Signature]

Date

1/21/97

Surveyor's Michigan License No.

30895