

SURVEY & REMONUMENTATION

APR 07 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 2 PAGE 126

For corners in

<u>Benzie</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>25N</u> R <u>15W</u>	<u>I-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

STATE OF MICHIGAN
BENZIE COUNTY
RECORDED

19 Jan 1998 9:36:01 AM
MICHELLE R. GRAY
REGISTER OF DEEDS
PAGES One

Register of Deeds Stamp & File Number

I, John B. Smendzuik, in a field survey on December 18, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	10	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

I-7: 1838: GLO set post - Beech 6" S30°E 29 links and Beech 15" N01°W 44 links. 1895: Frank S. Haswell, Surveyor's Record 1, Page 152, says he found old post and remains of witness tree and set cedar post 3' deep with crockery and glass around it. 1973: BCRC records show they found 12" of 1/2" pipe above a rotted wood stake and crockery. 1974: BCRC placed cast iron County marker over wood stake. 1976: Gourdie Fraser and Associates in a Certificate of Survey show an iron found and no witnesses. 1995: John Smendzuik, found cast iron County marker 4" below grade.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


I-7: 1997: Found 24" of cast iron County marker over 19" of 4" x 4" rotted cedar stake, 28" below road grade with glass, crockery and old plow point next to and around the wood stake. The Benzie County Peer Group accepted the Harrison marker over the wood stake as the perpetuation of the original GLO corner.

Ratified by Peer Group
In accordance with P.A. 345
Chairman [Signature]
Date 12/15/97

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-7: Removed the Harrison marker and the wood stake and set a 3" diameter Benzie County Remonumentation Program concrete monument with a brass cap, and left the glass and crockery around the monument, in a monument box.

- 24" Maple N35°E 44.59' to found 60D spike.
- 24" Maple S39°E 44.45' to found 60D spike.
- 10" Maple S12°W 36.17' to found 60D spike.
- 26" Twin Maple S16°E 35.71' to set 60D spike.
- Monument box is in centerline of Mick Road.



Signed by [Signature] Date 1/18/98
Surveyor's Michigan License No. 30895