

SURVEY & REMONUMENTATION

MAY 05 1997

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 2 PAGE 59
 STATE OF MICHIGAN
 BENZIE COUNTY
 RECORDED

For corners in **COMMISSION**

<u>Benzie</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>25N</u> R <u>15W</u>	<u>I-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

1/22/1997 1:56:46 PM
 MICHELLE R. GRAY
 REGISTER OF DEEDS
 # PAGES 1

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, **John B. Smendzuik**, in a field survey on 11/4/95 and 7/11/96, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I-11: G.L.O. set post and witnesses - 10" Sugar N73°W 21.78' and 8" Sugar S56°E 29.04'. Certificate of Survey by Bruce Jenema, dated August of 1993 shows found 1" pipe at corner.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-11: Found 1" iron pipe noted by Jenema on occupation line to north and in centerline of gravel road east and west.

Ratified by Peer Group
 In accordance with P.A. 345
 Chairman [Signature]
 Date 12/27/95

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-11: Removed 1" iron pipe and set 3" diameter Benzie County Remonumentation Program concrete monument 5" below grade of gravel road.

- 26" Maple N61°W 53.33'
- 25" Maple S30°E 25.23'
- 24" Maple S53°E 39.54'
- 48" Maple N61°E 39.45'

Signed by [Signature] Date 1/21/97
 Surveyor's Michigan License No. 30895