

SURVEY & REMONUMENTATION

APR 29 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE LIBER 2 PAGE 46
Filing Requirement of Act 74, Mich. P.A. 1970

or corners in

<u>Benzie</u> (County)	Located In:	Corner Code <u>I-5</u>
Public Land Survey	T <u>25N</u> R <u>16W</u>	<u>I-5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
Property Controlling in Section	S _____ T _____ R _____	_____
Miscellaneous	S _____ T _____ R _____	_____
Property in Sec.	S _____ T _____ R _____	_____

STATE OF MICHIGAN
BENZIE COUNTY
RECORDED
28 DEC 95 4:50 P.M.
MICHELLE R. GRAY
REGISTER OF DEEDS
Register of Deeds Stamp & File Number

Lot No. _____, Recorded Plat _____
Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

John B. Smendzuik in a field survey on 12/8-15/95, 19_____, hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Description of original monument and accessories and/or subsequent restoration:

I-5: G.L.O. Set post, 7" Birch S54½°E 12.54', 8" Hemlock N47°W 19.14'; Survey Record II, Page 70, Frank Haswell in 1908, drove a 4" cedar stake, 3' deep from original witness tree and old post. In 1965, Harold R. Bruning, old corner record, found axle shaft driven down through old cedar stake. Shaft and stake surrounded by pail filled with concrete. Bruning removed axle shaft and replaced it with 1" galv. iron pipe with brass cap and made new witnesses.

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-5: Found 1" galv. pipe with brass cap and witnesses as spelled out in Bruning record.

Ratified by Peer Group
In accordance with P.A. 346

Chairman [Signature]
Date 12/12/95

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-5: Removed 1" iron pipe and set 3" diameter Benzie County Remonumentation Program concrete monument.

- 8" soft Maple w/ blaze grown over N36°E 18.34'
- 1 1/4" Beech w/ blaze showing S29°E 29.50'
- 9" Hemlock w/ blaze grown over S30°W 43.45'
- 11" Hemlock w/ blaze grown over N52°W 42.69'

Signed by [Signature] Date 12/28/95
Surveyor's Michigan License No. 30895