

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
BENZIE COUNTY
RECORDED

BLAINE TOWNSHIP
For corners in

BENZIE COUNTY
(County)

Located In: Corner Code #

- | | | | |
|------------------------------------|---------------|---------------|--------------|
| 1. Public Land Survey | T <u>25</u> N | R <u>16</u> W | I- <u>11</u> |
| | T | R | |
| | T | R | |
| | T | R | |
| 2. Property Controlling in Section | S | T | R |
| | S | T | R |
| 3. Miscellaneous Property in Sec. | S | T | R |
| | S | T | R |

22 JAN 1999 3:00:16 PM
NICHELLE R. GRAY
REGISTER OF DEEDS
PAGES ONE

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, John B. Smendzuik, in a field survey on 12/7, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

I-11: 1838: GLO set post - Sugar 20" N32°W 44 links and Lynn 6" S35°E 35 links. 1882: Sam Davidson, Survey Record I, Page 128, shows corner in break of E 1/2 of Northeast 1/4. 1926: J. A. Pettit, copy of survey shows corner. 1959: Pierre O'Non copy of survey and notes from Nick O'non show found iron bar 0.28' West of square cedar stake. 1962: MDOT found 1" iron and 4 x 4" stake cedar stake and witnessed it. 1964: Harold R. Bruning found iron. 1969: Bill Richards, in proposed plat of Arcadia Highlands, shows found 1" square iron.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-11: 1998: Found a 1 x 1" x 32" iron bar with stones around it and fitting MDOT witnesses. No cedar stake or remains found. The Benzie County Peer Group accepted iron bar as the best evidence of the perpetuation of the original GLO corner.

Ratified by Peer Group
In accordance with P.A. 345
Chairman [Signature]
Date 11/19/98

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-11: Replaced the 1" square iron bar with a 3" diameter Benzie County Remonumentation Program concrete monument with a brass cap with stones around the base and sticking 5" above ground.

- 12" Ash N28°W 33.98' to set nail and BCRP tag.
- 9" Maple N24°E 19.49' to set nail and BCRP tag over found nail in blazed tree. (MDOT)
- 18" Maple S81°E 7.64' to set nail and BCRP tag in blazed tree. (MDOT)
- 13" Maple S32°E 12.38' to set nail and BCRP tag over found nail in blazed tree. (MDOT)
- 16" Cherry N52°W 23.29' to set nail and BCRP tag.

Signed by [Signature]
Surveyor's Michigan License No. 30895

Date 1/22/99