

**SURVEY &
REMONUMENTATION**

LIBER 2 PAGE 47

APR 29 1996

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

or corners in

<u>BENZIE</u> (County)	Located In:	Corner Code #
Public Land Survey	T <u>25N</u> R <u>16W</u>	<u>J-5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
Property Controlling in Section	S _____ T _____ R _____	_____
Miscellaneous Property in Sec.	S _____ T _____ R _____	_____

STATE OF MICHIGAN
BENZIE COUNTY
RECORDED
28 DEC 95 4:50 P.M.
MICHELLE R. GRAY
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

Lot No. _____, Recorded Plat _____
Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

John B. Smendzik in a field survey on 12/8-15, 1995,
I hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned
in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the
current manual of survey instructions of the United States Department of the Interior, Bureau of Land
Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5
above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a
Court of Law; established, re-established, monumented, re-monumented, recovered, found as
expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded
on this certificate.**

1. Description of original monument and accessories and/or subsequent restoration:

J-5: G.L.O. SET POST, 10" HEMLOCK S27°W 11.22', 10" HEMLOCK N19°W 5.94'; SURV. REC.
II, PAGE 70, FRANK HASWELL, IN 1908, FOUND CORNER FENCE POST AND AN IRON PIPE OK
FROM ORIGINAL WITNESSES. IN 1921, ASSESSOR'S PLAT OF BEUNA GLORIA, RECORDED IN LIBER
2 OF PLATS, PAGE 65, WAS Laid OUT FROM THIS CORNER. IN 1961, MDOT MADE A SEARCH FOR
CORNER IN AREA CUT FOR ROAD. COULD NOT FIND CORNER. MDOT SET A STONE LEG ON END IN
A MONUMENT BOX FROM TIES TO PLAT.

2. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-5: FOUND STONE LEG ON END IN A MONUMENT BOX FITTING EXISTING
MDOT WITNESSES.

Ratified by Peer Group
In accordance with P.A. 345
Chairman [Signature]
Date 12/12/95

3. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-5: REMOVED STONE LEG AND SET 3" Ø BENZIE COUNTY REMONUMENTATION PROGRAM
CONCRETE MONUMENT IN A MONUMENT BOX.

- 14" MAPLE N60°W 34.74'
- 13 HEMLOCK S42°W 32.83'
- 13" HEMLOCK S16°E 21.99'
- TWIN 15 & 18" MAPLE N03°W 35.81'

Signed by [Signature] Date 12/28/95
Surveyor's Michigan License No. 30895