

JAN 18 1999

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

BLAINE TOWNSHIP
For corners in

BENZIE COUNTY
(County)

Located In: Corner Code #

- 1. Public Land Survey T^{25N} R^{16W} J-9
- T R
- T R
- T R
- 2. Property Controlling S T R
- in Section S T R
- 3. Miscellaneous S T R
- Property in Sec. S T R

STATE OF MICHIGAN
BENZIE COUNTY
RECORDED

22 JAN 1999 3:00:39 PM
MICHELLE R. GRAY
REGISTER OF DEEDS
PAGES ONE

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, John B. Smendzuik, in a field survey on 12/8, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

J-9: 1838: GLO set post - Hemlock 12" N11°W 34 links and Sugar 12" S11°E 18 links. 1873: D. F. Holden, Survey Record I, Page 106 and 107, set from original bearing trees. 1959: Pierre O'Non copy of survey shows position for corner but no mention of what there. 1962: MDOT could not find the corner and set an axle shaft on a single proportionate measure between found corners at I-9 and K-9. 1972: Harold R. Bruning found the axle shaft in place and distance checks with MDOT.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-9: 1998: Found a 1" x 42" pointed axle shaft with gear on end per MDOT. Axle shaft fits 2 remaining MDOT witnesses still in place. The Benzie County Peer Group accepted the axle shaft as a replacement of the GLO position by single proportionate methods.

Ratified by Peer Group
In accordance with P.A. 345
Chairman [Signature]
Date 11/19/98

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-9: Replaced the axle shaft with a 3" diameter Benzie County Remonumentation Program concrete monument with a brass cap.

- 14" Ash S08°W 7.54' to found nail in blazed tree (MDOT witness).
- 15" Maple S33°E 15.89' to set nail and BCRP tag.
- 20" Beech N64°E 8.07' to found nail in blazed tree (MDOT witness).
- Hemlock stump N43°W 28.18' to found nail (MDOT witness).
- 7" Maple N82°W 10.98' to set nail and BCRP tag.

Signed by [Signature]
Surveyor's Michigan License No. 30895

Date 1/22/99