

JAN 28 1999

SECTION

BLAINE TOWNSHIP

For corners in

BENZIE COUNTY

(County)

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
BENZIE COUNTY  
RECORDED

22 JAN 1999 3:00:27 PM  
MICHELLE R. GRAY  
REGISTER OF DEEDS  
# PAGES ONE

Located In:

Corner Code #

1. Public Land Survey

T25N R16W

K-8

T R

T R

T R

2. Property Controlling  
in Section

S T R

S T R

3. Miscellaneous  
Property in Sec.

S T R

S T R

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, John B. Smendzuik, in a field survey on 12/9, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	19		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

K-8: 1838: GLO set post - Beech 12" N26°E 7 links and Beech 10" S53°W 11 links. Undated: Frank Haswell, Surveyor's Record 2, Page 72, says he planted iron and 1 1/4" iron pipe where original stake was. Also shows distance to north and to south. 1962: MDOT found a 1 1/4" iron pipe and witnessed it and used it for the P.I. of State Highway M-22.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-8: 1998: Found a 1" x 36" long galvanized iron pipe in a 2" x 15" iron stand, 12" below existing grade of gravel road and at the P.I. of M-22. Iron fits very well with Haswell distances to north and south. The Benzie County Peer Group accepted the 1" iron pipe found in the 2" stand as the best available evidence of the perpetuation of the original GLO corner.

Ratified by Peer Group  
In accordance with P.A. 345  
Chairman [Signature]  
Date 11/19/98

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-8: Replaced the 1" iron pipe with a 3" diameter Benzie County Remonumentation Program concrete monument with a brass cap, 6" below existing grade of Hunt Road.

32" Maple N22°E 74.70' to set nail and BCRP tag. (MDOT witness tree)  
Power Pole N84°E 117.17' to set nail and BCRP tag.  
24" W. Birch in clump of 4 N68°E 124.39' to set nail and BCRP tag.  
Road sign N43°W 46.88'.  
Monument is in centerline of Hunt Road and at the P.I. of State Highway M-22.

Signed by [Signature]  
Surveyor's Michigan License No. 30895

Date 1/22/99