

BLAINE TOWNSHIP
For corners in

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
BENZIE COUNTY
RECORDED

22 JAN 1999 3:01:03 PM
MICHELLE R. GRAY
REGISTER OF DEEDS
PAGES ONE

BENZIE COUNTY (County)	Located In:	Corner Code #
1. Public Land Survey	T25N R16W	L-11
	T___ R___	_____
	T___ R___	_____
	T___ R___	_____
2. Property Controlling in Section	S___ T___ R___	_____
	S___ T___ R___	_____
3. Miscellaneous Property in Sec.	S___ T___ R___	_____
	S___ T___ R___	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, John B. Smendzuik, in a field survey on 12/4, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

L-11: 1838: GLO set post - Maple 8" S19°30'E 30 links and Sugar 8" N50°W 27 links. GLO distances to the East and West are 2633.40'. 1873: D.F. Holden, Survey Record I, Page 106, set from original bearing trees. 1881-1882: Sam Davidson, Survey Record I, Page 122 and 123, did surveys from this location to occupations to the West. There are no other records that could be found regarding the location of this corner. Other information available and considered were the 1915 Atlas of Benzie County and the 1938 aerial photos.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-11: 1998: After much searching, compiling evidence and traversing through adjacent section corners, the Benzie County Peer Group and I settled on the following method for reestablishing this section corner. Once the section corner at K-11 was reestablished, it was determined that the distance from K-11 to M-11 was within 0.21' of the GLO distance. The recommendation was to set the corner at the single proportionate position between the corners at K-11 and M-11. This location wound up being on the old fence line occupation to the South. The Peer Group accepted this as the reestablishment of the corner per the GLO measure.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-11: Set a 3" diameter Benzie County Remonumentation Program concrete monument with a brass cap in a monument box.

16" Maple in clump S06°E 44.18' to set nail and BCRP tag.
Twin 10" W. Pine N64°W 62.28' to set nail and BCRP tag.
11" W. Pine N76°W 81.82' to set nail and BCRP tag.
Monument box is 3.8' North of the centerline of Joyfield Road.
No other witnesses available.

Ratified by Peer Group
in accordance with P.A. 345
Chairman [Signature]
Date November 19, 1998

Signed by [Signature]
Surveyor's Michigan License No. 30895

Date 1/22/99