

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 26 N. R. 13 W.	H-10
2. PROPERTY CONTROLLING IN SECTION	27 T. 26 N. R. 13 W.	9; 2
3. MISCELLANEOUS PROPERTY IN SECTION	T. N. R. E. S. W.	
4. LOT NO., RECORDED PLAT		
5. PRIVATE CLAIMS		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on November 17, 1980, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

XX

C. Continued:


- 2
- Fd Well Pt. Raised w/ 3/4"x1 1/2" Pipe
- Flush w/B.T. Rd.
- 13" W. Pine S43°E 63.41
- 6" W. Pine S35°W 94.98
- Ctr. of E-W B.T. Rd. North 3'
- Set Ced. Post w/loc Tag S 30'
- Cor. is in line w/old Fn. S

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- H-10 Established Ctr. of Sec. 27 at intersection of one-quarter lines. N-S fence is 4'± east. Old E-W field edge berm with fence mostly down is 19'± South.
- 9 Established SW Cor. of E 1/2 of NE 1/4 of S-27 equidistant & on line between ctr. & E 1/4 Cor's of S-27. Old E-W field edge berm with posts & wire(down) is 22'± South.
- 2 Accepted fd. well point for E 1/8 corner on North line of S-27. Fits with-in less than 1-ft. for midway & on line between fd 1/4 cor. to West & fd. 2-1/8 Ir's for Sec. Cor. to East.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-10	9
Set 5/8"x36" Re-Rod w/RLS Cap & ced Post w/loc Tag.	Set 5/8"x3' Re-Rod w/RLS Cap & Ced. Post w/loc Tag
16" Maple S60°W 140.2	3" Maple S56°E 64.8
8" Maple S11°E 132.7	10" Cherry S46°W 53.6
17" Maple S56°E 71.3	15" Ash(twin)N52°W 39.4
	Ctr. of N-S Winding Sand & Grave] Rd; E. 33'±



SIGNED BY Carl F. Roser 2/20/81 DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR

(SEAL)
 Inland Township
 BENZIE COUNTY

SURVEYOR'S MICHIGAN REGISTRATION NO. _____