

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 26 N. R. 13 W.	F-11; G-9
2. PROPERTY CONTROLLING IN SECTION	T. S. R. E. W.	
3. MISCELLANEOUS PROPERTY IN SECTION	T. S. R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on November 18, 1980, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- F-11 Re-estab. S 1/4 Cor., S-28, Equidistant and on line between SE & SW cor's of S-28.
- G-9 Fd. 3/4" pipe for NW Corner of S-27. Corner is in line with ctr. of bit. rd. tang. looking east. Two re-rod's with RLS Cap #13030 are 33'+ & 43.5'± East.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-11 Set. DNR Mon. & Ced. Post 10" Maple N06°W 48.8 8" Iron Wood(Triple) N83°E 28.0 13" Maple (Cluster) S11°E 19.9 9" Cherry S62°W 25.4	G-9 Fd. 3/4" Pipe (buried 0.3) *11" Ash N12°W 69.57 *10" Ash N35°W 43.67 in Ctr. Trail Rd. N Ctr. Trail Rd. S is W 18'± Ctr Bit Rd. on Curve S 41.5 Set Ced Post w/loc tag W 16.5
--	--

\* Old Witts


SIGNED BY Carl F. Roser 2/20/81 DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
MICHIGAN REGISTERED LAND SURVEYOR



SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_

Inland Township  
BENZIE COUNTY