

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	36 T. 26 N. R. 13 W.	M-11, M-12
2. PROPERTY CONTROLLING IN SECTION	36 T. 26 N. R. 13 W.	7
3. MISCELLANEOUS PROPERTY IN SECTION	T. N. R. E. W.	
4. LOT NO., RECORDED PLAT		
5. PRIVATE CLAIMS		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on November 18, 1980, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- 7 Cor established in 1971 Dept. Survey per standard B.L.M. instructions.
- M-12 ¼ cor. position established in 1971 Dept. survey in agreement with R.L.S. W. Fraser.
- M-11 This cor. established in 1971 Dept. survey. Corner is in approx. ctr. of N-S bit Surfaced road.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

7	M-12	M-11
Fd 1" pipe	Fd. Dept.Mon. in Mon. Box	Fd. Dept.Mon in Mon. Box
* 14" B. Cherry N88°W 49.7	* 8" Oak N67°E 66.7	*14" Oak S80°E 38.2
* 6" tri. Maple S50°E 73.3	*22" Oak N77°W 48.7	*12" Oak N40°E 72.1
* 4" Rd Conc.Mon.East 33.0'	*12" Maple N54°W 58.1	*P.Pole S80°W 41.0
ctr. N-S Blk top rd W 2'	ctr. N-S Blk.Top Rd. W 2'	Set Ced.Post w/loc tag East 33'

* 1971 Dept Wit's.
SIGNED BY Carl F. Roser 2/20/81 DATE _____



SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR

(SEAL)

Inland Township
BENZIE COUNTY

SURVEYOR'S MICHIGAN REGISTRATION NO. _____