

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 26 N. R. 13 W.	G-12; F-13; E-13;
2. PROPERTY CONTROLLING IN SECTION	T. N. R. W.	G-13
3. MISCELLANEOUS PROPERTY IN SECTION	T. N. R. W.	
4. LOT NO., RECORDED PLAT		
5. PRIVATE CLAIMS		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on November 18, 1980, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- G-12 Re-establish E 1/4 cor. of S-33, equidistant & on line between NE & SE cor's of S-33. An old over-grow E-W R.R. grade (in cut-section) **15** south 42'±.
- F-13 Re-establish S1/4 cor. of Sec. 33 mid-way & on line between SW & SE corners of S-33. The N 1/4 corner of Sec. 4, T25N-R13W, is S89°28'E 114.98'.
- E-13 Re-establish corner common to Sec's 32 & 33 on south line of T26N-R13W, by single proportion to G.L.O. survey (& on line) between found s 1/4 cor. of Sec 32 & found SE cor. of Sec. 36. The corner common to Sec's 4 & 5 on north line of T25N-R13W is S89°28'E 98.55'
- G-13 Re-establish corner common to Sec's 33 & 34 on south line of T26N-R13W by single proportion to G.L.O. survey (& on line) between fd. S1/4 cor. of sec.32 & fd SE cor. of Sec.36. The corner common to Sec's 3 & 4 on North line of T25N-R13W is S89°28'E 131.40'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-12 Set DNR mon. & cedar post 13" Maple N09°E 79.0 12" Maple(Twin)N63°E 2.7 6" Maple(Twin) S64°E 19.0 7" Maple(twin) S29°W 19.9	F-13 Set DNR mon. & Ced Post 11" Twin Maple N40°W 28.1 9" Maple N28°E 17.7	E-13 Set DNR mon & ced. post 12" Maple N80°E 14.4 5" maple N40°W 17.8
G-13 Set DNR Mon & Ced. Post 8" Maple N62°W 67.8 4" Maple N05°E 98.7		


SIGNED BY Carl F. Roser 2/20/81 DATE

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
MICHIGAN REGISTERED LAND SURVEYOR



SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_

*Inland Twp.  
Benzie County*