

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

| FOR CORNERS OF-- | LOCATED IN-- | CORNER CODE NUMBER |
|---------------------------------------|---------------------|--------------------|
| 1. PUBLIC LAND SURVEY | T. 26N N. R. 13W W. | D-3, D-4, D-5, E-5 |
| 2. PROPERTY CONTROLLING IN SECTION | T. S. R. E. W. | |
| 3. MISCELLANEOUS PROPERTY IN SECTION | T. S. R. E. W. | |
| 4. LOT NO. _____, RECORDED PLAT _____ | | |
| 5. PRIVATE CLAIMS _____ | | |

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, CARL F. ROSER, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 6-15, 1982, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

C. (CONT.)

| | |
|---|--|
| <p style="text-align: center;">D-5</p> <p>FD PK, REPL W/ 5/8"X36" REROD W/RLS CAP. 4" W PINE S30°E 64.90 8" H MAP S60°W 64.85 RD CONC MON SOUTH 33.00 CTR LINE US-31 NORTH 16.0 SO EDGE OF E-W BLKTOP RD (IN CURVE) NORTH 6.1</p> | <p style="text-align: center;">E-5</p> <p>FD 1" PIPE IN MON BOX. *T. POLE N27°E 78.08 *24" MAP STP N45°E 56.82 *24" MAPLE S70°E 121.80 *16" APPLE TREE S35°E 57.95 CTR US-31 S 2.7' CTR N-S GR RD E 7'± *= OLD WITS</p> |
|---|--|

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- D-3 FD. 1 1/4" PIPE (BURIED ONE FT) 2'± NORTH OF CTR. OF E-W GRAVEL ROAD.
- D-4 RECOVERED 5" DIA. POINTED CED POST BOTTOM (IN MUCK) FROM W. PINE B.T. STUMP (24" W.PINE STUMP - S76°30'E-15.2') PER OLD SURVEY OF RECORD BY D.F. HOLDIN, JAN-FEB, 1876, PGS. 112 & 113 OF "FIELD NOTES OF BENZIE CO & SURVEYORS RECORD" AT REG. OF DEEDS OFFICE. FITS WITHIN 2' FOR POSITION TO CALC. INTERSECTION OF 1/4 LINES. ACCEPTED CED POST BOTTOM FOR CTR. OF SEC. 8.
- D-5 FD. & ACCEPTED P.K. NAIL IN BLACKTOP WIDENING (US-31) AS PREVIOUSLY USED IN CERT. SURVEYS IN SEC. 17 BY RLS, H.BRUNING & RLS G.DELAMATER.
- E-5 FD 1" PIPE IN MONUMENT BOX FOR SE COR OF SEC 8.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

| | |
|---|---|
| <p style="text-align: center;">D-3</p> <p>FD 1 1/4" PIPE (BURIED 1'), RAISED W/ 3/8" SPK. *10" RED PINE S40°W 46.85 * 9" RED PINE DUE S 35.81 * 9" JACK PINE N35°W 41.87 SET CED POST W/LOG TAG S. 33' *= OLD WITS</p> | <p style="text-align: center;">D-4</p> <p>FD. POST BOTTOM ; DROVE 1"X36" PIPE INSIDE OLD 1 1/4"X36" PIPE & SET CED POST W/LOC TAG. 8" MAPLE N14°W 6.1 17" TW MAP S72°W 4.3 9" CEDAR S40°E 11.5 5" CEDAR S02°E 16.4 N-S 3-STD B-W IN TREES EAST 2'± SWP. EDGE (E-SW) NORTH 25'± N EDGE STANLEY CR (C-SW) SOUTH 63'±</p> |
|---|---|

SIGNED BY Carl F. Roser 6-28-82 DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

