

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
BENZIE

(County)

Located In: Corner Code ~~≠~~

1. Public Land Survey	T	<u>26N</u>	R	<u>13W</u>	_____
	T	_____	R	_____	_____
	T	_____	R	_____	_____
	T	_____	R	_____	_____
2. Property Controlling in Section	S	<u>30</u>	T	_____	_____
	S	<u>30</u>	T	_____	_____
3. Miscellaneous Property in Sec.	S	<u>30</u>	T	_____	_____
	S	<u>30</u>	T	_____	_____

*filed
8/7/88
97w*

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, CARL F. ROSE, in a field survey on JULY 8, 19 87, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

1	3	4	8
ESTAB'D NW COR OF NE 1/4 OF FRL NW 1/4 OF S-30, PER STANDARD BLM INSTRUCTIONS. NEWER E-W FN IS 168'± S; OLD E-W FN MOSTLY DOWN IS 46'± N.	ESTABLISHED NW COR OF THE FRL SW 1/4 OF FRL NW 1/4 OF S-30; PER STANDARD BLM INSTRUCTIONS.	ESTAB'D NE COR OF FRL SW 1/4 OF FRL NW 1/4 OF S-30, PER STANDARD BLM INSTRUCTIONS. FN COR (2 STRAND B.WIRE ON CED POSTS N & W) IS 27'± S & 320'±E OF OUR COR. FD OLD CED POST IN SWP, N01°10'W, 800'± ON OUR BDRY LINE.	FD PK FOR SE COR OF FRL SW 1/4 FRL NW 1/4 OF S-30; REPLACED WITH 5/8" REROD.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1	3	4	8
DROVE 5/8" X 34" REROD W/RLS CAP; SET CED POST W/LOC TAG. 3" OAK N60°W 99.0' 6" BASSWD IN CLUMP N20°W 47.5' 25" B CHERRY N50°E 110.0'	DROVE 1/2" X 13" GALV PIPE W/RLS CAP. FD 1 1/2"± PIPE LEANING & BURIED N1°27'E 26.7' 10" R PINE S60°E 43.59' POWER POLE S60°W 28.36' SW COR HSE FND N75°E 100.3' CTR BIT RD (N-S) DUE E 2.5' SET CED POST W/ LOC TAG EAST 33'	DROVE 5/8" X 34" REROD W/RLS CAP; SET CED POST W/LOC TAG. 4" MAPL-CLP 3 S60°E 53.05' 15" B CHERRY DUE S 41.87' 2" MPLE-CLP 3 S45°W 36.47' NO OTHER NITS AVAILABLE	FD P.K. BY RLS L.CZUBAK; REPLACED W/ 5/8" X 7" REROD. 8" R PINE N45°W 59.00' CTR 20' BIT RD DUE N 3' 5" MAPLE S50°W 46.63' 10" IRONWOOD S50°E 43.40' SET CED POST W/LOC TAG NORTH 33'

Signed by Carl F. Rose 8-29-88 Date _____
 12028
 Surveyor's Michigan License No. _____

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS

