

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Benzie Located In: Corner Code #
 (County)

1. Public Land Survey T 26N R 13W B-3
 T R
 2. Property Controlling S T R
 in Section S T R
 3. Miscellaneous S T R
 Property in Sec. S T R

Register of Deeds Stamp & File Num

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Craig W. McVean, in a field survey on July 14, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- B-3 - GLO - Set ¼ post - Alvin & Austin Burt - 1839
 Beech 10" N12°E 24L
 Hem. 10" S20°W 5L
- Co. Sur. Bk., P. 109 - D.F. Holden - 1875
 Set post from original BT's
- DNR Project # 71-6 - Carl Roser - 1971
 FND. ¼" Pipe & Crockery buried in S'ly edge of E-W gravel Rd.
 Added DNR Mon. Set Cedar post w/ Loc. tag Due S. 33'.
 8" W. Pine N64°E 66.23'
 4" W. Pine S46°E 35.92'
 7" W. Pine S48°W 40.75'
- DNR Project # 31-93100 - Carl Roser - 1981
 - Rec. Survey - L. 1, P. 868 - R.M. Harris - 1986
 FND. Mon.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- B-3 - ¼ Corner common to Sec.'s 6&7, T26N,R13W. FND. ¾"x 2.5' long Iron Pipe w/ Crockery around; down 28", 2'± N. of CL. E-W gravel Rd. FND. 4" DNR Alum. Cap on 1"x 36" long Iron Pipe alongside 0.08' N. & 0.04' E. Accept ¾" Iron Pipe as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- B-3 - Replace ¾" Iron Pipe & DNR Mon. w/ Benzie Co. Concrete Monument, down 0.8'.
 Placed broken crockery around base of Monument as a memorial
 North 33.08' to PS Cap # 25845 on ½" Rebar. Set blue Carsonite post w/ Loc. tag alongside
 South 33.6' to face 5" Cedar post w/ Loc. tag
 *S34°W 50.37' to set N&T in NW. Side 9" W. Pine - scribed 'XBT'
 S40°E 52.23' to set N&T in NE. Side 14" W. Pine - scribed 'XBT'
 *N38°E 51.29' to set N&T in SE. Side 15" W. Pine - scribed 'XBT'

*FND. nail & shiners by others



Signed by Craig W. McVean
 Surveyor's Michigan License No. 39088

Date 9/30/1998