

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In:				
<u>Benzie</u>	<u>Located In</u>	<u>Corner Code #</u>		
(County)				
1. Public Land Survey	T _____ R _____			
	T _____ R _____			
2. Property Controlling in Section	S 5 T 26N R 13W	7		
	S 5 T 26N R 13W	CENE 1/64		
3. Miscellaneous Property in Section	S _____ T _____ R _____			
	S _____ T _____ R _____			

Register of Deeds Stamp & File Number

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Craig W. McVean, in a field survey on Aug 5, 1998 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6					4		3		2		1	
3													
4	7							10		11		12	
5													
6	18					16		15		14		13	
7													
8	19					21		22		23		24	
9													
10	30					28		27		26		25	
11													
12	31					33		34		35		36	
13													

Description of original monument and accessories and/or subsequent restoration:

Z - None CENE 1/64 - None



B. Description of corner evidence found and/or method applies in restoring or re-establishing corner:

Z - N 1/16 Corner common to Sec.'s 4&5, T26N,R13W
Set 2" Alum. Cap on 5/8" x 34" Rebar per Standard BLM procedure. Monument in river bottom-land - 63' N of the N bank of Platte River.

CENE - 1/64 - Sec. 5 - Set 2" Alum. Cap on 5/8" x 34" Rebar per Standard BLM procedure. Monument falls on S slope into Platte River valley.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Z - 2" Alum. Cap on 5/8" x 34" Rebar
N6°E 20.95' to N&T in E. Side 10" Cedar
N81°E 15.85' to N&T in S. Side 10" Cedar
S12°E 35.77' to N&T in E. Side 17" Y. Birch
S19°W 18.99' to N&T in W. Side Tw. 7" R. Maple
S65°W 9.9' to fnd. steel fence post
Set blue Carsonite post 1' NE.

CENE - 1/64 - 2" Alum. Cap on 5/8" x 34" Rebar
S73°W 21.88' to N&T in N. Side 4" R. Maple
N76°E 18.01' to N&T in N. Side 6" R. Maple
N42°E 23.50' to N&T in NW. Side 6" R. Maple
N19°W 22.47' to N&T in W. Side 6" R. Maple
Set blue Carsonite post 1' NW.

Signed by: Craig W. McVean
Surveyor's Michigan License No.: 39088

Date: 10/6/1998