

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Benzie</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S <u>6</u> T <u>26N</u> R <u>13W</u>	<u>5</u>
	S <u>6</u> T <u>26N</u> R <u>13W</u>	<u>6</u>
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Register of Deeds Stamp & File Num.,

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Craig W. McVean, in a field survey on May 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1	•	•										
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- | | |
|---|---|
| <u>5</u> - Geo. Steele - 1868 - Beech 4" for Corner,
Sugar 36" N87°E 25 L. - Sub. of NE 1/4, Sec. 6
Co. Petition Survey, Old Bk. Pg. 89-90. | <u>6</u> - Geo. Steele - 1868 - Maple 6" S6 1/2°W 19L
Sugar 6" N65 1/2°W 20L - Sub. of NE 1/4, Sec. 6
Co. Petition Survey, Old Bk. Pg. 89-90. |
|---|---|

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- | | |
|--|---|
| <u>5</u> - C - N 1/16 Sec. 6 - FND. no conclusive evidence of Geo. Steele Cor. position. Set 2" A.C. on 5/8" x 34" Rebar by prorating to G. Steele distances between B1 & B2. Fences remains N-S is 6' ± W, and fence remains to E are 7' ± S. | <u>6</u> - NE 1/16 Sec. 6 - FND. no conclusive evidence of Geo. Steele's post. Set 2" A.C. on 5/8" x 34" Rebar per Standard BLM Procedure. Corner of Down Fences E, W&N is S40°W 7.6' ±. N-S Sand Road is 29'E. |
|--|---|

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|--|--|
| <u>5</u> - 2" Alum. Cap on 5/8" x 34" Rebar with Carsonite Post and Ring of Stone.
N66°W 15.97' to N&T in S. Side 6" R. Pine
N6°E 16.05' to N&T in E. Side 7" R. Pine
N62°E 23.33' to N&T in NW Side 10" R. Pine
S56°W 18.73' to N&T in SE Side 9" R. Pine | <u>6</u> - 2" Alum. Cap on 5/8" x 34" Rebar with Carsonite Post Guard.
N66°W 32.66' to N&T in S. Side 10" R. Pine
N54°E 72.92' to N&T in SE Side 8" R. Pine
S6°E 102.37' to N&T in E. Side 8" R. Pine
S20°W 69.46' to N&T in W. Side 7" Cherry |
|--|--|

Signed by Craig W. McVean Date 9/30/1998
 Surveyor's Michigan License No. 39088

