

**SURVEY & REMONUMENTATION**

MAY 05 1997

LIBER 2 PAGE 52

**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
 BENZIE COUNTY  
 RECORDED

For corners in **COMMISSION**

<u>Benzie</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>26N</u> R <u>13W</u>	<u>A-5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

1/22/1997 1:55:18 PM  
 MICHELLE R. GRAY  
 REGISTER OF DEEDS  
 # PAGES 1

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	16		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, John B. Smendzuik, in a field survey on 4/11 and 6/26, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

A-5: G.L.O. set post and witnesses - 11" Sugar N72°30E 27.06, 9" Sugar S75°E 33.66', 14" Sugar N20°W 6.60' and 12" Beech S13°W 9.90'. Survey by G.A. Shadko, Michigan Department of Conservation, in June of 1944, found a SQUARED stake and an iron 33' to east. Shadko set a DNR concrete monument. Act 74 record by Carl F. Roser in Liber 1, Page 132, shows Shadko corner found.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-5: Found DNR brass cap and a concrete monument 4' long.

Ratified by Peer Group  
 In accordance with P.A. 345  
 Chairman [Signature]  
 Date 12/27/95

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-5: Removed DNR monument remains, after Road Commission work to rebuild County Road 669, and set 3" diameter Benzie County Remonumentation Program concrete monument in monument box in road intersection.

- |                               |                               |
|-------------------------------|-------------------------------|
| 24" Maple N58°W 47.95'        | 5/8" x 24" rebar S44°W 75.27' |
| 17" Maple S51°E 43.91'        | 10" Ash N86°E 31.17'          |
| 5/8" x 24" rebar N44°E 75.14' |                               |

Signed by [Signature] Date 1/21/97  
 Surveyor's Michigan License No. 30895