

SECTION

LAND CORNER RECORDATION CERTIFICATE LIBER 2 PAGE 225
Filing Requirement of Act 74, Mich. P.A. 1970

INLAND TOWNSHIP
For corners in
BENZIE COUNTY
(County)

Located In: Corner Code #

- 1. Public Land Survey T 26N R 13W F-3
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
- in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Sec. S _____ T _____ R _____
- 4. Lot No. _____ Recorded Plat _____
- 5. Private Claims _____

STATE OF MICHIGAN
BENZIE COUNTY
RECORDED

22 JAN 1999 3:05:19 PM
MICHELLE R. GRAY
REGISTER OF DEEDS
PAGES ONE

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

John B. Smendzuik, in a field survey on September 30, 19 98, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

F-3: 1839: GLO set post - Sugar 18" S10°W 12 links and Sugar 9" N13°E 32 links. 1880: D. F. Holden, reset from original witnesses. 1959: Bill Batzer section break shows iron found. 1979: Harold Bruning, Unrecorded survey, Job No.: 79-2264, shows spike found and witnesses it. 1997: Max Harris, Certificate of Survey, Liber 2, Page 838, shows a found 1/2" iron.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-3: 1998: Found 1/2" x 18" iron rod, fitting Max Harris witnesses and close to Batzer distances, approximately 8" below grade in 'T' intersection of Fewins and Burnt Mill Roads. The Benzie County Peer Group accepted the 1/2" iron rod as the best evidence of a locally accepted corner.

Ratified by Peer Group
In accordance with P.A. 348
Chairman [Signature]
Date 9/28/98

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-3: Pulled the 1/2" iron rod and set a 3" diameter Benzie County Remonumentation Program concrete monument with a brass cap approximately 6" below grade of gravel road. Fewins Road was later paved and a monument box was placed over the monument by the BCRC.

- 10" R. Pine S07°E 54.81' to found 60D spike and blaze.
- 9" R. Pine S44°E 56.29' to found 60D spike and blaze.
- 4" J. Pine N47°E 60.71' to found nail and tag with blaze.
- Stop sign N31°W 55.85'.
- Monument box is in the center of a 'T' road intersection, Fewins and Burnt Mill Roads.

Signed by [Signature] Date 1/22/99
Surveyor's Michigan License No. 30895