

MAR 9 2000

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. PA 1970

SECTION

Form with fields: For Corners In: Benzie (County), Located In, Corner Code #. Includes sections for Public Land Survey, Property Controlling in Section, Miscellaneous Property in Section, Lot No., and Private Claims.

STATE OF MICHIGAN
BENZIE COUNTY
RECORDED

12 JAN 2000 9:22:34 AM
MICHELLE R. GRAY
REGISTER OF DEEDS
# PAGES One

Register of Deeds Stamp & File Number

Grid table with columns A-M and rows 1-13. A black dot is located at the intersection of column G and row 7.

I, Craig W. McVean, in a field survey on November 3, 1999 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G7- GLO- set Post Alvin & Austin Burt- 1839
Beech 6" S7°E 28 L.
Beech 10" N2°W 27 L.
-D.F. Holden- 1876- Mon. Extinct- Burned to ground. Not reset because of snow
-C.P. Tuller- 1903- chained between I7 & E7 & from G6 to Line Tree S. of G7. (By DBL. Proportion) Set Aspen Post 48" x 5" x 5"- 24" in ground and standing out 24" and dug pit 36" x 36" x 12" in 8' N. of

corner and raised a mound 4' x 2' high- 4' N. of corner. W. Pine Stp. 40" S62°W 32', W. Pine Stp. 36" S87°W 21'
-LCRC #164- H.R. Bruning- 1982- set Iron Rod w/ RLS cap using Record Tuller dist. to G6 & 1/2 corner to east. H. Maple 6" S27°W 56.62', Trp. Maple 6" S68°W 58.78', Tw. Maple 8" N39°W 45.24', W. Pine 6" N75°E 26.35'

B. Description of corner evidence found and/or method applies in restoring or re-establishing corner:

G7- Sec. Corner common to Sec. 15, 16, 21 & 22- FND. Capped 1/2" Iron Rod per H. Bruning in N-S Sand Rd. Dig 9' x 9' area in Sand Rd. looking for evidence of Tuller Post- nothing FND.- Searched for Tuller's BT stps, but nothing found. Accepted HB Capped Iron as the best available evidence of the position of the original corner.

Ratified by Peer Group
In accordance with P.A. 345

Chairman [Signature]
Date 11/2/1999

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G7 - Replaced 1/2" x 24" capped rebar w/ 3" 'Benzie Co. Remon.' Brass Cap on 3/4" x 36" Iron pipe encased in 4" x 36" conc. cylinder - down 0.8'
S19°W 56.68' to set N & T in E. side 12" R. Maple (HB)
S84°W 41.02', to set N & T in S. side Quad 13" R. Maple
N45°W 45.04' to set N & T in NE side 12" R. Maple (HB)
N69°E 26.35' to set N & T in S side 10" W. Pine(HB)
East 33.02' to set 2" A.C. on 5/8" x 3/4" Rebar on line & Blue Carsonite Post w/ loc. tag



Signed by: [Signature of Craig W. McVean]
Surveyor's Michigan License No.: 39088

Date: 12/8/99