

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

INLAND TOWNSHIP SECTION
For corners in
BENZIE COUNTY (County)

STATE OF MICHIGAN
BENZIE COUNTY
RECORDED

22 JAN 1999 3:06:03 PM
MICHELLE R. GRAY
REGISTER OF DEEDS
# PAGES ONE

Table with columns: Located In, Corner Code #, and rows for Public Land Survey, Property Controlling in Section, and Miscellaneous Property in Sec.

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

Grid table with columns A-M and rows 2-13, containing numbers 1-36 and a central dot at row 3, column H.

I, John B. Smendzuik, in a field survey on September 30, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules thereore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

H-3: 1839: GLO set post - Beech 5" S15°E 16 links and Beech 7" N12°E 32 links. 1897-1904: James Pettit, Survey Records II, Page 14, set double gun barrel MOL between adjacent section corners. 1980: BCRC found a double gun barrel, 3' long, 0.15' south and 0.15' west of a wooden stake set in a dug hole with topsoil in it. BCRC replaced the gun barrel with 30" of 1 1/4" pipe. 1993: Max Harris, unrecorded survey shows a found 1/2" iron bar and witnessed it.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-3: 1998: Found 5/8" x 28" iron bar stuck in 1 1/4" x 30" iron pipe, per the BCRC, approximately 4" below grade of existing gravel road. The Benzie County Peer Group accepted the position of the gun barrel, now the 1 1/4" x 30" iron pipe as being the best evidence of a locally accepted corner.

Ratified by Peer Group
In accordance with P.A. 345
Chairman [Signature]
Date 9/28/98

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-3: Pulled the 5/8" iron rod and the 1 1/4" iron pipe and set a 3" diameter Benzie County Remonumentation Program concrete monument with a brass cap approximately 6" below grade of gravel road. Fewins Road was later paved and a monument box was placed over the monument by the BCRC.

- Telephone Pole S47°E 48.62' to found 60D spike.
Fence Post S48°W 51.09' to found 60D spike.
10" Red Pine N15°W 37.75' to found 60D spike.
10" Red Pine N49°E 52.07' to found 60D spike and blaze.
Monument box is in the centerline of Fewins Roads.

Signed by [Signature]
Surveyor's Michigan License No. 30895

Date 1/22/99