

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

INLAND TOWNSHIP
For corners in
BENZIE COUNTY
(County)

Located In: Corner Code #

STATE OF MICHIGAN
BENZIE COUNTY
RECORDED

22 JAN 1999 3:06:31 PM
MICHELLE R. GRAY
REGISTER OF DEEDS
# PAGES ONE

- 1. Public Land Survey T 26N R 13W I-4
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R
4. Lot No. Recorded Plat
5. Private Claims

Register of Deeds Stamp & File Number

Grid with columns A-M and rows 2-13. Cell 4,10 contains a black dot.

I, John B. Smendzuik, in a field survey on September 29, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I-4: 1839: GLO set post - Sugar 20" N69°E 66 links and Sugar 15" S48°W 49 links. 1919: James Pettit, Survey Record II, Page 14, notes that corner previously established by Slawson. 1985: Harold Bruning, Job No.: 85-2843, found a plow point and witnesses it. 1986: Robert Mitchell, Certificate of Survey in Liber 1, Page 869, shows found plow point and witnesses it. 1987: Robert Mitchell, LCRC in Liber 1, Page 227 shows same as survey. 1993: Max Harris ties into the corner and witnesses it.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-4: 1998: Found a plow point that fit Mitchell, Bruning and Harris witnesses. The Benzie County Peer Group accepted the position of the plow point as being the best evidence of a locally accepted corner.

Ratified by Peer Group
In accordance with P.A. 345
Chairman [Signature]
Date 9/28/98

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-4: Pulled the plow point and set a 3" diameter Benzie County Remonumentation Program concrete monument with a brass cap approximately 4" below grade of asphalt road. Reynolds Road was later repaved and a monument box was placed over the monument by the BCRC.

- 10" W. Pine N88°W 61.11' to found 60D spike.
10" R. Pine N63°W 49.51' to found 60D spike.
11" R. Pine N59°E 41.40' to found 60D spike and blaze.
14" Maple in clump of 3 S64°E 41.09' to found 60D spike and blaze.
Monument box is in the centerline of Reynolds Roads, just north of centerline of Chappel Trail, a private road to the West.

Signed by [Signature] Date 1/22/99
Surveyor's Michigan License No. 30895