

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
BENZIE COUNTY
RECORDED

22 JAN 1999 3:03:19 PM
MICHELLE R. GRAY
REGISTER OF DEEDS
PAGES ONE

For corners in

BENZIE COUNTY
(County)

Located In:

Corner Code #

INLAND TOWNSHIP

- | | | |
|---------------------------------------|---------------------------|--------------|
| 1. Public Land Survey | T <u>26N</u> R <u>13W</u> | <u>I - 6</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

Register of Deeds Stamp & File Number

I, John B. Smendzuik, in a field survey on December 2, 19 98, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

I-6: 1837: GLO set post - Hemlock 15" N66°W 11 links and Beech 5" S71°E 19 links. 1905-1906: Langford, Survey Record 2, Page 50, Gaspipe 2.5 feet long. Undated: D.F. Holden measured distance of 2643.96 feet to North. 1974: Bill Batzer, LCRC in Liber 1, Page 185, set 1/2"x24" iron in centerline of road midway between right of way fences and approximately 3' south of Holden distance to North. 1974: Bill Batzer, Certificate of Survey and section break recorded in Liber 1, Page 379, same as above. 1982: Harold Bruning, LCRC in Liber 1, Page 165, recorded found iron the same as Batzer's. 1991: Max Harris, unrecorded LCRC shows 1/2" rod in monument box. The road was rebuilt at this point in time. 1996-97: Michigan DNR section work, found iron in monument box.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-6: 1998: Found 1/2"x 18" rebar in monument box over a 1/2" x 24" rebar with cap No. 13026 as per Batzzer LCRC. The Benzie County Peer Group accepted the rebar in the monument box as the best evidence of the perpetuation of the reestablishment of the original GLO corner.

Ratified by Peer Group
In accordance with P.A. 845
Chairman John B. Smendzuik
Date 11/23/98

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-6: Pulled the rebar and the rebar with Batzer cap and set a 3" diameter Benzie County Remonumentation Program concrete monument with a brass cap in a monument box.

- 26" Maple N50°E 41.18' to set nail and BCRP tag.
 - 1/2 x 18" iron with cap No. 25845 West 33.00'.
 - 24" Maple N80°E 37.83' to set nail and BCRP tag.
 - 10" and 16" Twin Cherry S73°W 43.65' to found nail and old tag.
- Monument box is in the centerline of Reynolds Road and on an occupation line to the East and West.

Signed by John B. Smendzuik Date January 22, 1999
Surveyor's Michigan License No. 30895