

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

INLAND TOWNSHIP

For corners in

BENZIE COUNTY
(County)

Located In:

Corner Code =#

- | | | | | | |
|------------------------------------|---|-----|---|-----|-----|
| 1. Public Land Survey | T | 26N | R | 13W | I-8 |
| | T | | R | | |
| | T | | R | | |
| | T | | R | | |
| 2. Property Controlling in Section | S | | T | R | |
| | S | | T | R | |
| 3. Miscellaneous Property in Sec. | S | | T | R | |
| | S | | T | R | |

STATE OF MICHIGAN
BENZIE COUNTY
RECORDED

22 JAN 1999 3:03:43 PM
MICHELLE R. GRAY
REGISTER OF DEEDS
PAGES ONE

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, John B. Smendzuik, in a field survey on December 1, 19 98, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I-8: 1837: GLO set post - Hemlock 7" N24°W 27 links and Hemlock 9" S24°E 33 links. 1866: George Steele from road survey records shows distance from G-9 to I-8 of 5855.52. (DNR survey computes to 5869.65'). 1978: Glen DeLamater, Certificate of Survey shows found broken off well point on fence to East and 9' East of centerline of gravel road. 1983: Bill Batzer, Certificate of Survey recorded in Liber 1, page 764, shows found 1 1/2" iron pipe same as DeLamater. 1988: BCRC found 1 1/2" iron pipe. 1991: Max Harris, unrecorded LCRC shows 1/2" rod in monument box. The road was rebuilt at this point in time. 1991-1993: Various surveyors used the iron in the monument box. 1996-97: Michigan DNR section work, found iron in monument box in centerline of road.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-8 1998: Found 1/2"x 24" rebar in 1 1/4" x 12" iron pipe with a 1/2 x 18" rebar inside the pipe in a monument box per Harris LCRC and in centerline of Reynolds Road. The Benzie County Peer Group accepted the rebar in the monument box as the best evidence of the perpetuation of the reestablishment of the original GLO corner.

Ratified by Peer Group
In accordance with P.A. 345
Chairman [Signature]
Date 11/23/98

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-8: Pulled the rebar and pipe and set a 3" diameter Benzie County Remonumentation Program concrete monument with a brass cap in a monument box.

- 8 and 20" Maple S73°E 41.45' to set new nail and BCRP tag over old nail.
- G.T. Survey Co. iron and cap by steele fence post East 33.00'.
- 20" Ash N40°W 52.58' to set nail and BCRP tag.
- Power Pole West 56.73' to found 50D spike.
- Monument box is in the centerline of Reynolds Road.

Signed by [Signature] Date 1/22/99
Surveyor's Michigan License No. 30895