

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

INLAND TOWNSHIP
For corners in
BENZIE COUNTY
(County)

STATE OF MICHIGAN
BENZIE COUNTY
RECORDED

22 JAN 1999 3:04:19 PM
MICHELLE R. GRAY
REGISTER OF DEEDS
PAGES ONE

Register of Deeds Stamp & File Number

Form with fields for 'Located In:', 'Corner Code #', and numbered items 1-5 describing survey details.

Grid table with columns A-M and rows 2-13, containing numbers 1-36 and a central dot.

I, John B. Smendzuik, in a field survey on December 1, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
J-9: 1837: GLO set post - Sugar 12" S34°W 35 links and Sugar 28" N55°E 14 links. 1970 Glen DeLamater set iron and cap MOL between adjacent section corners. 1980: BCRC found iron and cap which fits DeLamater witnesses. 1983: Bill Batzer, Certificate of Survey in Liber 1, Page 764, found DeLamater cap and iron, 4' North of centerline of road and 6.5 feet West of fence line to the north. 1992: Max Harris Certificate of Survey shows found iron and cap. 1996-97: Michigan DNR section work, found 1" iron and cap at Batzer position.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
J-9: 1998: Found 1/2"x 18" iron bar with unreadable cap in west bound lane of Cinder Road, 4' North of centerline of road and West of fence to north. The Benzie County Peer Group accepted the iron and cap as a locally accepted corner.

Ratified by Peer Group
In accordance with P.A. 345
Chairman [Signature]
Date 11/23/98

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
J-9: Pulled the iron and cap and set a 3" diameter Benzie County Remonumentation Program concrete monument with a brass cap in a monument box.

- Power Pole N44°E 38.84' to set nail and BCRP tag.
Michigan Bell phone riser post S38°E 47.74' to found pk nail.
8" R. Pine S27°W 56.39' to set nail and BCRP tag over found 60D spike.
8" J. Pine N16°E 49.89' to set nail and BCRP tag.
Monument box is in the westbound lane of Cinder Road.

Signed by [Signature] Date 1/22/99
Surveyor's Michigan License No. 30895