

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
BENZIE COUNTY
RECORDED

22 JAN 1999 3:04:31 PM
MICHELLE R. GRAY
REGISTER OF DEEDS
PAGES ONE

Register of Deeds Stamp & File Number

INLAND TOWNSHIP

For corners in
BENZIE COUNTY

Located In: Corner Code #

1. Public Land Survey	T	26N	R	13W	K-7
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Sec.	S		T	R	
	S		T	R	

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

John B. Smendzuik, in a field survey on December 2, 19 98, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
K-7: 1837: GLO set post - Sugar 24" N22°W 25 links and Elm 14" S35°E 28 links. 1868: George Steele, Survey Record I, Page 90-91, shows distance to East of 2595.12'. 1905-1906: Guy Langford in Survey Record II, Page 50, shows cedar post 4x4x2.5' long. 1980: BCRC found 1" solid iron bar 8" deep and raised it with a RR spike. 1983: Bill Batzer, Certificate of Survey in Liber 1, Page 764, found RR spike. 1980-1994: Various surveyors in area used RR spike in Certificates of Survey. 1996-97: Michigan DNR section work, found RR spike at Batzer position and is long of Steele's distance.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
K-7: 1998: Found RR spike over a boat spike over a 15x15" granite stone with barely discernable paint on side, approximately 20" below road grade. The Benzie County Peer Group accepted the RR spike position as a locally accepted corner.

Ratified by Peer Group
In accordance with P.A. 345
Chairman [Signature]
Date 11/23/98

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
K-7: Pulled the RR spike, boat spike and granite stone and set a 3" diameter Benzie County Remonumentation Program concrete monument with a brass cap in a monument box.

- Power Pole S23°W 97.42' to found PK nail.
- 12" R. Pine S60°W 78.70' to found 60D spike.
- 36" Maple S48°E 85.55' to set nail and BCRP tag.
- 28" Maple S42°W 99.48' to set nail and BCRP tag.
- Monument box is in the intersection of St. John's and Bendon Road.

Signed by [Signature] Date 1/22/99
Surveyor's Michigan License No. 30895