

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

INLAND TOWNSHIP
For corners in
BENZIE COUNTY
(County)

Located In: Corner Code #

- 1. Public Land Survey T 26N R 13W K-8
T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____
- 4. Lot No. _____ Recorded Plat _____
- 5. Private Claims _____

STATE OF MICHIGAN
BENZIE COUNTY
RECORDED

22 JAN 1999 3:04:43 PM
MICHELLE R. GRAY
REGISTER OF DEEDS
PAGES ONE

Register of Deeds Stamp & File Number

I, John B. Smendzuik, in a field survey on December 2, 19 98, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

K-8: 1837: GLO set post - Sugar 12" S65°W 17 links and Sugar 7" N65°E 27 links. 1891: Frank Haswell, Survey Record I, Page 135, shows "located post and old witness to NE and right tree to South, planted Post". 1976: Harold Bruning found a 1" iron. 1980: BCRC found 1 1/8" solid iron rod 12" deep. Also found 1" iron rod to South per plat of Bendon. 1980: Perla Stout and Associates found 1 1/4" iron bar and witnessed it. 1983: Bill Batzer, Certificate of Survey in Liber 1, Page 764, found 1" iron bar. 1991-1994: Various surveyors in area used iron bar in Certificates of Survey. 1996-97: Michigan DNR section work, found 1 1/4" iron bar at Batzer position.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-8: 1998: Found 1" x 30" wagon axle, approximately 12" below road grade. The Benzie County Peer Group accepted the wagon axle as the best evidence of the perpetuation of the original GLO corner.

Ratified by Peer Group
In accordance with P.A. 345
Chairman [Signature]
Date 11/23/98

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-8: Pulled the wagon axle and set a 3" diameter Benzie County Remonumentation Program concrete monument with a brass cap in a monument box.

Max Harris iron and cap West 33.00'
13" Aspen S74°E 30.18' to found 50D spike.
12" R. Pine N56°E 49.45' to found 60D spike.
9" Aspen S32°W 59.80' to found 50D spike.
Monument box is in the centerline of Bendon Road.

Signed by [Signature] Date 1/22/99
Surveyor's Michigan License No. 30895