

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 2 PAGE 223

INLAND TOWNSHIP

For corners in

BENZIE COUNTY
(County)

Located In:

Corner Code #

- 1. Public Land Survey T 26N R 13W K-9
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
- in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Sec. S _____ T _____ R _____

STATE OF MICHIGAN
BENZIE COUNTY
RECORDED

22 JAN 1999 3:04:55 PM
MICHELLE R. GRAY
REGISTER OF DEEDS
PAGES ONE

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, John B. Smendzuik, in a field survey on December 1, 19 98, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-9: 1837: GLO set post - Maple 10" S69°W 17 links and Maple 14" N29°E 20 links. 1892: Frank Haswell, per the recorded plat of Bendon, shows he perpetuated the corner by an iron point set from the original bearing trees. 1964: Harold Bruning, Old section corner records, Page 65, found a 1 1/4" iron pipe and pieces of broken crockery at corner. 1976: Bruning shows a 1 1/4" iron pipe in a Certificate of Survey. 1980's: DNR worksheet shows they found the 1 1/4" iron pipe. 1980-1994: Various surveyors in area used iron pipe in Certificates of Survey. 1996-97: Michigan DNR section work, found 1 1/4" iron pipe in dirt road intersection with stones and crockery around it.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-9: 1998: Found 1 1/4" x 43" iron pipe, surrounded by cobble stones with 11" of 1" iron bar and large plow point along side of main iron pipe, approximately 5" below road grade. The Benzie County Peer Group accepted the 1 1/4" iron pipe as the best evidence of the perpetuation of the original GLO corner.

Ratified by Peer Group
In accordance with P.A. 345
Chairman [Signature]
Date 11/23/98

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-9: Pulled the 1 1/4" iron pipe, iron bar and plow point and set a 3" diameter Benzie County Remonumentation Program concrete monument with a brass cap and with the cobble stones around the base of it.

- P.I. of Bendon Road, a 1" solid iron, S46°E 5.85'.
- 10" Maple N57°E 31.48' to found 60D spike.
- 26" Oak S73°W 36.56' to set nail and BCRP tag over found nail and tag.
- 11" S. Maple S64°W 43.51' to found 60D spike.
- 11" S. Maple N69°W 47.12' to found 60Dspike.
- 'T' iron fence post West 4.11'
- Monument is in the center of a dirt road 'T' intersection.

Signed by [Signature] Date 1/22/99

Surveyor's Michigan License No. 30895