

SECTION LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

INLAND TOWNSHIP

For corners in
BENZIE COUNTY
(County)

Located in:	Corner Code #
T <u>26N</u> R <u>13W</u>	<u>L-9</u>
T _____ R _____	_____
T _____ R _____	_____
T _____ R _____	_____
T _____ R _____	_____
S _____ T _____ R _____	_____
S _____ T _____ R _____	_____
S _____ T _____ R _____	_____
S _____ T _____ R _____	_____

STATE OF MICHIGAN
BENZIE COUNTY
RECORDED

22 JAN 1999 3:05:07 PM
MICHELLE R. GRAY
REGISTER OF DEEDS
PAGES ONE

Register of Deeds Stamp & File Number

- 1. Public Land Survey
- 2. Property Controlling in Section
- 3. Miscellaneous Property in Sec.
- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, John B. Smendzuik, in a field survey on December 1, 19 98, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

L-9: 1837: GLO set post - Maple 12" N46°W 13 links and Maple 13" S39°E 9 links. 1980's: DNR worksheet shows they found a 1" iron pipe with a 2" head approximately 12" below grade and raised it with a 1" x 12" iron pipe. 1982: Jack Gavin, Certificate of Survey, Liber 2, Page 308 shows distance to West. 1994: Max Harris: Certificate of Survey, Liber 2, Page 453, shows same distance and found 1" iron pipe. 1995: Neil Livasy, Certificate of Survey, Liber 2, Page 582, found 1" iron pipe and witnessed it. 1996-97: Michigan DNR section work, found 1" iron pipe in east-west paved road.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-9: 1998: Found 3/4" x 12" iron pipe over 1 1/2" x 27" iron rod with 2" knob on top, approximately 13" below road grade. The Benzie County Peer Group accepted the 3/4" iron pipe as the best evidence of a locally accepted corner.

Ratified by Peer Group
In accordance with P.A. 345
Chairman [Signature]
Date 11/23/98

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-9: Pulled the 3/4" iron pipe and the iron rod and set a 3" diameter Benzie County Remonumentation Program concrete monument with a brass cap in a monument box.

- 20" Maple N17°E 37.29' to found 50D spike.
- 12" W. Poine N34°W 46.19' to found 60D spike.
- 17" W. Pine N50°E 49.32' to set nail and BCRP tag over found 60D spike.
- Power Pole S38°E 32.40' to set nail and BCRP tag.
- Monument box is in the center of Rhodes Road.

Signed by [Signature] Date 1/22/99
Surveyor's Michigan License No. 30895