

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Benzie Located In: Corner Code #
 (County)

1. Public Land Survey T 26N R 13W E-7
 T _____ R _____
 2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____
 3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Craig W. McVean, in a field survey on Aug. 12, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

E-7 - GLO - Set post - Alvin & Austin Burt - 1839
 Cedar 14" S69°E 12 L. -Unrecorded Survey - File # 94-3334 - R.M. Harris - 1994
 Cedar 9" N61°W 36 L. FND. DNR Mon.
 - C.M. Cade - 1939 - Survey Sec. 17
 - LCRC - L.1, P. 161 - C. Roser - 1982
 Set DNR Mon. by DBL. down distance & on line,
 Across Cades Mon's
 for 1/8 Cor. & 1/4 Cor. to N. which fits fd. Cade Mon's
 & his survey for S. Line of Sec. 17. Cor. also fits US
 tie to definite swp. edge to W. Exactly & US tie to Swp.
 edge to S. within 20'. Add Cedar post.
 10" Cedar S20°W 5.6'
 20" W. Pine S65°E 9.9'
 9" Cedar N20°W 39.5'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-7 - Corner common to Sec.'s 16, 17, 20, & 21, T26N,R13W. - FND. DNR 4" Alum. Cap on 1" Iron Pipe as recorded in cedar swamp. FND. 6" cedar post 1' NW. & 3" sq. cedar post 0.7' N. Monument accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-7 - DNR 4" Alum. Cap on 1" Iron Pipe
 *S20°W 6.00' to set N&C in E. Side 11" Cedar
 *S77°E 10.98' to set N&T in N. Side 22" W. Pine
 *N15°W 39.90' to set N&T in E. Side 9" Cedar
 N69°W 29.90' to set nail in S. Side 10" Cedar - scribed 'XBT'
 N20°E 12.61' to set Nail in W. Side 8" Cedar - scribed 'XBT'
 Set blue Carsonite post 1' E.
 *Old CFR BT's - old distance to base blaze - scribed 'NBT'



Signed by Craig W. McVean
 Surveyor's Michigan License No. 39088

Date 12/8/1999