

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Benzie Located In: Corner Code #
 (County)

1. Public Land Survey T 26N R 13W F-7
 T _____ R _____

2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Craig W. McVean, in a field survey on November 3, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

F-7 - GLO - Maple 10" dia. - 1/4 Cor. - Alvin & Austin Burt - 1839
 Hemlock 12" N5°W 39 L.
 - Co. Bk., P. 8 - C.P. Tuller - 1900
 Found the stump of the Maple corner
 and the stump of the Hemlock witness.

- Co. Bk., Pg. 22 - C.P. Tuller - 1903
 Retraced S. line of Sec. 15 & 16
 No mention of S 1/4 Post, Sec. 16

-LCRC - L. 1, P. 312 - R.M. Harris - 1994
 Conc. Monument & steel post set
 (Proportionate to GLO)
 Tw. 16" Oaks S36°W 54.59'
 6" Maple N7°E 4.01'
 6" W. Pine S78°W 75.14'
 14" Maple S37°E 48.84'
 43' North of Two Track Road

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-7 - 1/4 Corner common to Sec.'s 16&21, T26N,R13W. - FND. 4" Cyl. Conc. Mon. w/ Plastic PS Cap # 25845 per RMH
 LCRC - L. 1, P. 312. FND. fence post on ground in hole 2'± SW'ly. Could find no evidence of corner tree per
 Tuller's 1900 survey. Tuller's 1903 survey done to establish the SE Cor. of Sec. 16 & the S 1/4 Cor. of Sec. 15 - makes
 no mention of S 1/4 Cor. of Sec. 16, but used SW Cor. of Sec. 16 to prorate 2 miles to the East. Accept Conc. Mon. as
 a careful & faithful re-establishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-7 - Replaced capped 4" x 2.5' long conc. mon. with 3" 'Benzie Co. Remon.' Brass Cap on 3/4" x 36" iron pipe encased in
 4" x 36" concrete cylinder
 *S30°W 54.56' to set N&T in NW. Side 16" Twin R. Oak
 *N2°E 3.99' to set N&T in E. Side 5" R. Maple
 *S74°W 75.12' to set N&T in N. Side 7" W. Pine
 *S40°E 49.88' to set N&T in SW. Side 12" S. Maple
 N54°E 118.43' to set N&T in NW. Side 4" W. Pine
 Set Blue Carsonite post 1' N.
 Reset steel fence post 1' S.

*RMH witnesses, our N&T set next to his.



Signed by Craig W. McVean
 Surveyor's Michigan License No. 39088

Date 12/8/1999