

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Benzie</u>	Located In:	Corner Code #
(County)		
1. Public Land Survey	T <u>26N</u> R <u>13W</u>	<u>H-6</u>
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Craig W. McVean, in a field survey on Feb. 9, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		●		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

H-6 - Co. Bk., P. 113 - Set post - D.F. Holden - 1876
 Sugar 12" S15°45'W 30L
 Sugar 12" S52°E 12L



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-6 - C1/4 Sec. 15, T26N,R13W. Search for evidence of post - nothing found. Set 2" Alum. Cap on 5/8"x 34" Rebar at the intersection of 1/4 lines, fence remains E&W. Monument accepted as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-6 - 2" Alum. Cap on 5/8"x 34" Rebar - stamped 'C1/4S15 1998'
 N83°E 34.15' to CL. 1" W. Pine
 S3°E 64.40' to N&T in E. Side 12" S. Maple (Clp. 5)
 S32°E 76.72' to N&T in NE. Side 4" R. Pine
 N85°W 46.80' to H.B. Cap # 10681 on 1/2" Rebar
 S63°W 74.80' to N&T in N. Side 16" Douglas Fir
 Set blue Carsonite post 1' SE.

Signed by Craig W. McVean
 Surveyor's Michigan License No. 39088

Date 3/29/2000