

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Benzie</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S 15 T 26N R 13W	11
	S 15 T 26N R 13W	12
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Craig W. McVean, in a field survey on Feb. 10, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

11 - None 12 - None

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

11 - SW1/16, Sec. 15, T26N, R13W
Set 2" Alum. Cap on 5/8"x 34" Rebar per standard BLM procedure.

12 - C-S1/16, Sec. 15, T26N, R13W
Set 2" Alum. Cap on 5/8"x 34" Rebar per standard BLM procedure.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

11 - 2" Alum. Cap on 5/8"x 34" Rebar
S75°E 12.51' to N&T in S. Side 8" Tw. S. Maple
S46°E 48.09' to N&T in SW. Side 7" W. Pine
S23°W 45.92' to N&T in NW. Side 12" W. Pine
N66°W 43.58' to N&T in NE. Side 7" W. Pine
Set blue Carsonite post 1' SE.

12 - 2" Alum. Cap on 5/8"x 34" Rebar
N15°W 27.60' to N&T in W. Side 13" W. Pine
N43°E 64.38' to N&T in SE. Side 10" W. Pine
S26°E 20.80' to N&T in E. Side 4" R. Maple
S10°W 46.86' to N&T in E. Side Tw. 9" B. Cherry
Set blue Carsonite post 1' SE.



Signed by Craig W. McVean
 Surveyor's Michigan License No. 39088

Date 3/29/2000