

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Benzie</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S 16 T 26N R 13W	5
	S 16 T 26N R 13W	6
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

**Register of Deeds Stamp & File Number**

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, Craig W. McVean, in a field survey on Feb. 12, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

5 - None 6 - None

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

5 - C-N1/16, Sec. 16, T26N,R13W  
Set 2" Alum. Cap on 5/8"x 34" Rebar  
Per Standard BLM procedure.

6 - NE1/16, Sec. 16, T26N,R13W  
Set 2" Alum. Cap on 5/8"x 34" Rebar  
Per Standard BLM procedure.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

5 - 2" Alum. Cap on 5/8"x 34" Rebar  
N27°E 36.12' to N&T in SE. Side 9" R. Pine  
S73°E 51.99' to N&T in N. Side 11" W. Pine  
S31°E 37.14' to N&T in W. Side 19" W. Pine  
S72°W 80.75' to N&T in N. Side 5" W. Pine  
Set blue Carsonite post 1' S.

6 - 2" Alum. Cap on 5/8"x 34" Rebar  
S76°E 90.16' to N&T in N. Side 8" R. Pine  
N20°E 33.73' to N&T in W. Side Tw. 10" S. Maple  
S81°W 36.32' to N&T in N. Side 8" S. Maple  
S27°W 38.42' to N&T in E. Side 2" W. Pine  
Set blue Carsonite post 1' SW.



Signed by Craig W. McVean  
 Surveyor's Michigan License No. 39088

Date 3/29/2000