

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Benzie</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S 22 T 26N R 13W	12
	S 22 T 26N R 13W	13
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____



4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Craig W. McVean, in a field survey on Aug. 6 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 12 - Jenema Land Surveys #90378 - 1/2" Iron w/cap Set - 1990.
- 13 - Jenema Land Surveys #90378 - 1/2" Iron w/cap Set - 1990.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 12 - CS 1/16 Corner, Sec. 22 - FND. PS Cap #25850 on 1/2" x 18" Rebar per B. Jenema Survey. Fits standard BLM procedure position within reason. E-W Cedar Posts for old fence is 25 + N. Monument accepted as the best available evidence of the position of the corner.
- 13 - SE 1/16 Corner, Sec. 22 - FND. PS Cap #25850 on 1/2" x 18" Rebar per B. Jenema Survey. Fit Standard BLM Procedure position within reason. Monument accepted as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 12 - Replace Cap 1/2" Rebar with 2" A.C. on 5/8" x 34" Rebar with Carsonite Post 1' N. N57°E 51.68' to N&T in NW Side 11" R. Oak S63°E 33.15' to N&T in N. Side 6" R. Oak S3°E 70.61' to N&T in W. Side 4" R. Oak N82°W 70.83' to N&T in N. Side 6" R. Oak
- 13 - Replace capped 1/2" Rebar with 2" A.C. on 5/8" x 34" Rebar with Carsonite Post 1'NW. N37°E 20.73' to N&T in W. Side 3" R. Oak N37°W 51.28' to N&T in SW Side 15" R. Oak N65°W 135.32' to N&T in Side 15" R. Oak S12°E 117.04' to NW Cor. Blk. Gar. FNDDT. of HSE.

Signed by Craig W. McVean
 Surveyor's Michigan License No. 39088

3/29/00
 Date

