

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In:
Benzie Located In _____ Corner Code # _____
 (County)

- | | | | | |
|--------------------------------------|-------------|--------------|--------------|----------|
| 1. Public Land Survey | T _____ | R _____ | | |
| | T _____ | R _____ | | |
| 2. Property Controlling in Section | S <u>25</u> | T <u>26N</u> | R <u>13W</u> | <u>4</u> |
| | S <u>25</u> | T <u>26N</u> | R <u>13W</u> | <u>5</u> |
| 3. Miscellaneous Property in Section | S _____ | T _____ | R _____ | |
| | S _____ | T _____ | R _____ | |

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Craig W. McVean, in a field survey on Sept 8, 1998 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:
 4 - None 5 - None



B. Description of corner evidence found and/or method applies in restoring or re-establishing corner:
 4 - NW 1/16 cor. Sec. 25 – Corner in cedar swamp. Set 2" Alum. Cap on 5/8" x 34" Rebar per standard BLM procedure.
 5 - CN 1/16 Cor. Sec. 25 – Set 2" Alum. Cap on 5/8" x 34" Rebar per standard BLM procedure.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 4 - 2" Alum. Cap. on 5/8" x 34" Rebar
 Set Blue Carsonite Post 1' SW
 N70°E 26.16' to N & T in SE side 6" Cedar
 N52°W 13.35' to N & T in SW side 6" Cedar
 S40°W 10.00' to N & T in SE side 9"W. Birch
 S20°E 21.49' to N & T in E side 3" Fir
 5 - 2" Alum. Cap on 5/8" x 34" Rebar. Added broken glass around and set Blue Carsonite Post 1' SE.
 S19°E 21.72' to N & T in W. side 42" R. Oak
 N83°W 15.83' to N & T in S. side 4" R. Oak
 N60°E 40.77' to N & T in SE side 14" S. Maple
 S85°E 18.76' to N & T in S side 4" W. Pine

Signed by: Craig W. McVean Date: 3/29/2000
 Surveyor's Michigan License No.: 39088