

# LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: <u>Benzie</u> (County)	Located In	Corner Code #
1. Public Land Survey	T <u>26N</u> R <u>13W</u>	<u>E8</u>
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No: _____	Recorded Plat: _____	
5. Private Claims: _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Craig W. McVean, in a field survey on June 13, 2007 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

E8 – **1839** – GLO – Alvin and Austin Burt  
 Set ¼ post  
 1) Beech 14" S37°W 49 L.  
 2) Beech 10" East 17 L.

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

E8 – ¼ Corner common to Sections 20 & 21 – No GLO evidence found. Set stamped 3" Benzie Co. Remon. Brass Cap monument by single proportion to GLO between 'E7' and 'E9'. Grid distance North and South is 2698.06' (2640' – GLO). Centerline of meandering N-S 2-track is 52' East. Benzie Co. Mon. accepted as the best available evidence of the position of the original corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

E8 – Stamped 3" Benzie Co. Remon. Brass Cap on ¾" x 36" iron pipe encased in 4" x 36" concrete cylinder.  
 S3°E 12.08' to set Nail & Tag (N & T) in E. side 13" R. Oak scribed 'XBT'  
 N2°E 27.80' to set N & T in E. side 3" W. Pine  
 N53°W 32.42' to set N & T in SW side 11" W. Pine scribed 'XBT'  
 S72°W 85.67' to set N & T in SW side 11" W. Pine scribed 'XBT'  
 Set Blue Carsonite Post 1' N.



Signed by: Craig W. McVean  
 Surveyor's Michigan License No.: 39088

Date: 12/11/2007