

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 26 N.R. 14 W


Benzie COUNTY

DESCRIPTION OF CORNER 1/4 corner common to Sections 9 and 16

CORNER MONUMENT Drove 1" x 24" pipe

DATE MONUMENT PLACED AND WITNESSED Jan. 5, 1966

WITNESSES TO CORNER.....



14" Elm S 56 E 24.9'

8" Ash S 63 W 8.6'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was set while making a survey of Sec. 16. Placed corner as prescribed by possible southwest USBT stump, which falls exactly at old fence corner north and east. Unable to positively identify as original witness, but is considered likely that old fence was constructed to the corner. This position is in general area of a previous iron pipe noted by local residents in past but obviously been removed, since no sign of it can presently be found. Appears to be best available evidence of proper location for that corner.

SURVEYOR'S SEAL

SIGNED

Kenneth J. Ostling
REGISTERED LAND SURVEYOR #10068

DATE January 19, 1966