

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 26 N.R. 14


Benzie COUNTY

DESCRIPTION OF CORNER 1/4 corner common to Sections 15 and 16

CORNER MONUMENT Set 1" pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED January 5, 1966

WITNESSES TO CORNER.....



7" Hemlock N27W 10.5'

9" H. Maple N64 E 22.2'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was set while making a survey in Section 16. Set corner in old E-W fence line, about 48 links east of a fence corner E-W and north. This falls in line with old established fence along the north 20 chains between 15 and 16 and about 2 rods east of a fence along the east line of the SE-NE

SURVEYOR'S SEAL

SIGNED *Levett H. Stetham* DATE January 19, 1966
REGISTERED LAND SURVEYOR #10068