

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>26</u> ^{N.} <u>●</u> , R. <u>14</u> ^{W.} <u>●</u>	<u>C-4; D-4; D-5</u>
2. PROPERTY CONTROLLING IN SECTION _____	, T. _____ ^{N.} <u>●</u> , R. _____ ^{W.} <u>●</u>	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ ^{N.} _____, ^{S.} _____, R. _____ ^{E.} _____, ^{W.} _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on April 1, 1977, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- C-4 Found iron in monument box per MSHD plans dated 1932.
- D-4 Found nail per Co. Surv. H. Bruning, RLS, certificate survey of part of NE-SW Sec. 8. This fits 0.2' south of straight line E-W 1/4 line between fd. W 1/4 Sec. 8 (mon. box in pavement) & fd. 1" pipe at probable E 1/4 Sec. 8. Also fits F. Haswell survey of SW 1/4 Sec. 8 in 1895 very close.
- D-5 Recovered "T" iron as set by RLS H. Bruning to perpetuate fd. column of black dirt believed to mark 1/4 corner per F. Haswell survey of SW 1/4 Sec. 8 dated 1895.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-4	D-4	D-5
Found iron bar in mon. box	Found nail in b'top (US-31)	Fd. 3/4" "T" iron w/cap; ^{set} cedar post w/loc. tag
P. Pole S42°E 45.54	Fd. rerod w/RLS cap	26" Maple S68°W 64.38
P. Pole N21°E 104.80	S00°26'33"E 38.85	7" R. Pine S57°E 40.75
12" Maple N21°W 82.00	Fd. rerod w/RLS cap	P. Pole S33°W 65.75
Ctr. US-31 Due N 3.9	S80°20'03"W 199.82	In approx. line w/fence remains E & Ctr. of gravel rd. N&W
	Fd. B spk. Hwy. P.I.	
	S89°45'59"E 708.56	
	P. Pole S12°E 41.09	
	P. Pole N06°E 53.43	

SIGNED BY Carl F. Roser

DATE 10-31-77

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028


FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____
CHIEF OF SURVEY PARTY

DATE _____

APPROVED AND SIGNED BY _____
MICHIGAN REGISTERED LAND SURVEYOR

DATE _____



(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____
HOMESTEAD TOWNSHIP
BENZIE COUNTY