

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

3

FOR CORNERS OF --	LOCATED IN --	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 26 N. R. 14 W.	B-13; C-13
2. PROPERTY CONTROLLING IN SECTION 31	T. 26 N. R. 14 W.	15
3. MISCELLANEOUS PROPERTY IN SECTION	T. N. S. R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on June 12, 1978, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

B-13 Fd. Benzie County Monument, S 1/4 Cor. Sec. 31, buried in E-W dirt County Road. Fits Frank S. Haswell Sur. of Sec. 31, dated Oct. 1909.

C-13 Restored Sec. Cor. Comm. to Sec's. 31&32, So. Line T26N-R14W, at double distance & on line across fd. 1/4 Cor. & 1/8 Cor. to west, per Frank S. Haswell survey of Sec. 31 dated Oct. 1909.

15 Recovered 1 1/4" pipe, buried, for W. 1/8 Cor. on South line of Sec. 31; per F. Haswell Survey of Sec. 31 in 1909. The W. 1/8 Cor. on N. line S-5(25-14) is N89°36'E, 69.61'.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-13	C-13	15
Fd. Benzie Co. Mon.	Set DNR Mon. (Buried)	Fd. 1 1/4" pipe (buried) &
11" R. Pine N56°E 64.48	10" Maple S50°W 37.0	Set Ced. Post w/Loc. Tag
15" Cherry S21°W 51.82	8" Maple S12°W 74.8	3" Iron wood N32°W 29.6
27" Maple S70°W 77.78	5" Ir. Wood S27°E 55.9	9" Iron wood N60°W 48.6
Ctr. E-W dirt rd. Due S 10'+	Ctr. E-W dirt Co. Rd.	Ctr. E-W Dirt Rd.
Set Ced. Post w/Loc. Tag.	Due S 4'	Due S 17'+
Due N 16.5'	Cor. to Sec's. 5&6(25-14)	
N 1/4 Cor.	S89°38'E 276.70	
S-5(25-14) N89°37'E 139.16	Set Ced. Post w/Loc. Tag.	
	Due N. 29'	

SIGNED BY Carl F. Roser 2-12-79 DATE

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028


FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____

MICHIGAN REGISTERED LAND SURVEYOR



(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

BENZIE COUNTY