

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>BENZIE</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>26N</u> R <u>14W</u>	<u>I-2</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S <u>3</u> T ___ R ___	<u>1004' N of</u>
	S ___ T ___ R ___	<u>I-2</u>
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, CARL T. KIISKILA, in a field survey on DECEMBER 10 92 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		●	2		1	
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

I-2 1004' N OF I-2
 U.S. G.L.O. (1839) - SET OR SECTION POST.
 BEECH 6 N15°E 8
 DO 9 S19°W 31

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 I-2 1004' N OF I-2

FD 5/8" REROD FOR E1/4 COR OF SEC. 3. H. DRUNING SET THIS CORNER
 PROPORTIONATE MEAS. AND ON LINE BETWEEN NE & SE SEC. CORNERS.
 12-21-73. CTR OF N-S WINDING DIRT RD IS 360' +/- 10' WEST.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-2	1004' N OF I-2
FD 5/8" REROD, ADDED CEDAR POST.	SET 5/8" x 3/4" REROD W/PS CAP & CEDAR POST.
114° BASSWOOD N05°W 87.62'	14° S. MAPLE N20°W 8.2'
118° TRI.B. CHERRY S65°E 14.84'	5° S. MAPLE EAST 11.4'
17° S. MAPLE S20°E 46.81'	10° S. MAPLE S30°E 13.6'
SET 5/8" x 3/4" REROD W/PS CAP & CEDAR POST N00°15'W 1004.28'	

1 = RLB, H. DRUNING, 1973 BT'S.

Signed by Carl T. Kiiskila
 Surveyor's Michigan License No. 33981

Date 4-9-97