

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

BENZIE

(County)

Located In:

Corner Code #

1. Public Land Survey

T 26R 14W _____
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling
 in Section

S 2 T _____ R _____
 S _____ T _____ R _____

3. Miscellaneous
 Property in Sec.

S 3 T _____ R _____
 S _____ T _____ R _____
528' N of CODE 7

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, CARL T. KIISKILA, in a field survey on DECEMBER 12-19 92 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5			4		3		2		1
3													
4	7			8			9		10		11		12
5													
6	18			17			16		15		14		13
7													
8	19			20			21		22		23		24
9													
10	30			29			28		27		26		25
11													
12	31			32			33		34		35		36
13													

A. Description of original monument and accessories and/or subsequent restoration:

3 528' N of 7

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

3 528' N of 7

ESTABLISHED THE NW COR OF SW1/4 OF FRL. NW1/4 OF S-2 ON LINE BETWEEN NW & N1/4 COR OF S-2 PRORATED TO PETTIT, CO. SURVEYOR, 1897; WHICH EQUALS CLOSE TO PROPORTIONATE MEASURE TO GLO 1837. CTR OF N-S ROAD IS 5' WEST.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

3 528' N of 7

SET 5/8" x 3/4" REROD W/PS CAP.	SET 5/8" x 3/4" REROD W/PS CAP & CEDAR POST.
10" S. MAPLE N65°W 28.6'	11" MAPLE N60°W 6.5'
6" S. MAPLE N60°E 17.6'	10" MAPLE N55°E 31.6'
12" S. MAPLE S30°E 24.2'	12" MAPLE S15°W 8.5'
8" TRI. S. MAPLE S55°W 29.4'	CTR. OF N-S WINDING ROAD IS EAST 8'.
SET CEDAR POST W/LOC TAG EAST 10'	
SET 5/8" x 3/4" REROD W/PS CAP AND CEDAR POSTS: N00°15'W, 528.18'	
& 892.21'.	

Signed by Carl T Kiiskila
 Surveyor's Michigan License No. 33981

Date 4-9-97