

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

BENZIE

(County)

Located In:

Corner Code #

1. Public Land Survey

T 26N R 14W H-1  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling in Section

S 3 T \_\_\_\_\_ R \_\_\_\_\_ 9  
 S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous Property in Sec.

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, CARL T. KIISKILA, in a field survey on AUGUST 27, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

H-1  
 H. BRUNING, R.L.S. #10681 SET PK NAIL BY SINGLE PROPORTIONATE BETWEEN 6-1 & I-1 IN 1974; L.C.R.C. L. 1, P. 91.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

ACCEPTED FD 1 1/8" DIAMETER X 18" LONG IRON ROD FOR N1/4 COR S-3 BURIED 4" AT EXACT EDGE OF E-W BIT ROAD IN CURVE. PS, CARL ROSEY SET THIS IRON IN 1975 IN PLACE OF FD PK NAIL, RLS HAROLD BRUNING CORNER OF RECORD. FD 5/8" COR OF S3/4 OF SE1/4 OF FRL NE1/4 OF S-3. CORNER FITS H. BRUNING 1973 PROPER SECTION SUBDIVISION. E-W 2-TRACK IN VALLEY IS 145' SOUTH.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-1  
 FD 1 1/8" x 18" IRON ROD. FD 5/8" REROD W/RLS CAP, ADDED CEDAR POST W/LOC TAG.  
 #28° S. MAPLE S66°E 34.30' 9° S. MAPLE N05°E 24.6'  
 #34° S. MAPLE S43°E 39.00' 14° S. MAPLE S60°E 7.1'  
 #FD R.R. SPIKE (RD PI) N60°W 12.03' 6° S. MAPLE S35°W 21.1'  
 SET CARSONITE POST W/LOC TAG SOUTH 33'  
 S1/4 COR S-34, T27N-R14W, BENZIE CO RENOM. PROGRAM MON IN MON  
 BOX IS N89°20'W 10.20'

# = PS, C.F. ROSEY 1975 WIT.

Signed by Carl T. Kiiskila  
 Surveyor's Michigan License No. 33981

Date 4-9-97

