

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>BENZIE</u>	Located In:	Corner Code #
(County)		
1. Public Land Survey	T <u>26N</u> R <u>14W</u>	<u>K-1, L-1</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, CARL T. KIISKILA, in a field survey on AUGUST 14, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	10		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

K-1 L-1  
 U.S. G.L.O. - INTERSECT NORTH BOUNDARY 32 LKS EAST OF CORNER &  
 SET POST COR SEC'S 1 & 2.  
 HEMLOCK 36 S26°W 14  
 SUGAR 12 S15°E 34  
 JUNE 4, 1839

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-1 L-1  
 REESTABLISHED THE NW COR OF SEC. 1, T26N-R14W AT RECORD U.S.  
 G.L.O. DIST. (21.1') EAST OF RE-ESTABLISHED SEC COR TO SEC 35 &  
 36, T27N-R14W & ON LINE BETWEEN SW & S1/4 COR'S OF SEC. 36,  
 T27N-R14W.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

<u>K-1</u>	<u>L-1</u>
SET DNR MON & CARSONITE POST W/LOC TAG.	SET DNR MON & CARSONITE POST.
16" TRI.R.MAPLE N16°E 8.23'	4" S.MAPLE N10°W 4.62'
14" TRI.R.MAPLE S22°E 58.14'	8" S.MAPLE N30°E 17.94'
8" TRI.S.MAPLE S46°W 10.38'	12" S.MAPLE S60°E 14.94'
CTR N-S SAND RD WEST 29'	4" S.MAPLE S35°W 2.84'
SW S-36, T27N-R14W, SET 1"x 48" GALV. PIPE	S1/4 COR S-36, T27N-R14W, SET BENZIE CO REMON
W/PS CAP N89°00'W 21.10'	PROGRAM MON. N89°00'W 10.55'

Signed by Carl T Kiiskila  
 Surveyor's Michigan License No. 33981

Date 4-9-97