

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>BENZIE</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>26</u> R <u>14</u> W	<u>I-3, J-1</u>
	T <u>    </u> R <u>    </u>	<u>    </u>
	T <u>    </u> R <u>    </u>	<u>    </u>
	T <u>    </u> R <u>    </u>	<u>    </u>
2. Property Controlling in Section	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
3. Miscellaneous Property in Sec.	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, CARL T. KIISKILA, in a field survey on AUGUST 14, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

I-3  
 U.S. G.L.O. (1839) - SET POST CORNER OF SEC'S 2-3-10 & 11.  
 BEECH 12 S49°W 10(6.6')  
 DO 12 N13°E 29(19.1')  
 J-1



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-3  
 FD 5/8" REROD FOR SE COR OF SEC. 3. IN 1974 PS, H. BRUNING "SET PROPORTIONATE TO OLD SECTION SURVEY MADE BY J. PETTITT". CTR OF N-S SAND ROAD IS 2' WEST. CTR OF SAND ROAD TO WEST IS 11' NORTH.  
 J-1  
 RECOVERED OLD 1" WELL POINT AND ADDED DNR MON IN EXACT SAME POSITION FOR N1/4 COR SEC. 2. IN 1907 CO. SURVEYOR F. HASWELL "SET 1" GALV. IRON WELL POINT 27 1/2 LINKS EAST OF 1/4 POST FOR TOWN 27N R14W".

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-3	J-1
FD 5/8" REROD.	FD 1" WELL POINT ADDED DNR MON & SET CARSONITE POST.
36" S. MAPLE N45°W 47.49'	28" B. CHERRY N32°E 12.37'
13" TN. S. MAPLE N50°E 48.70'	18" TN. MAPLE N70°E 26.70'
12" MAPLE S30°E 50.89'	11" R. PINE S37°W 41.28'
16" S. MAPLE S50°W 50.97'	S1/4 COR S-35, T27N-R14W, DNR MON, N88°37'W 18.15'
SET CARSONITE POST W/LOC TAG EAST 16.5'	

‡ = PS, H. BRUNING 1974 MIT.

Signed by Carl T. Kiiskila Date 4-9-97  
 Surveyor's Michigan License No. 33981