

MAR 09 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

LIBER 2 PAGE 262

Form with fields: Benzie (County), Located In, Corner Code #, 1. Public Land Survey, 2. Property Controlling in Section, 3. Miscellaneous Property in Sec., 4. Lot No., 5. Private Claims

STATE OF MICHIGAN
BENZIE COUNTY
RECORDED

5 JAN 2000 3:27:07 PM
MICHELLE R. GRAY
REGISTER OF DEEDS
# PAGES one

Register of Deeds Stamp & File Number

I, David T. Rowe, in a field survey on October 19, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

Grid table with columns A-M and rows 1-13. A dot is present in row 5, column K.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-5: 1/4 Corner Common to Sections 11, 12, 13 and 14:
G.L.O. Notes: 1839 Set 1/4" Set Post. 12" Sugar S26°E° 28lks, 14" Hemlock N9°W 14lks.
County records: 1944 G. Shadko, Fd. Iron pin in monument box
1973 H. Burning, L.I., page 85, iron pipe in monument box. 14" Maple S23°E 74.05', 14" Maple S55°E 134.55', P. Pole S30°W 65.72',
1977 B. Batzer, Recorded Surveys, L.I., page 741, Fd. 1/2" iron in monument box. S29°W 65.62' P. Pole, S25°E 82.22' 6" Maple, North 2.35' center-line road

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-5: 1/4 Corner Common to Sections 11, 12, 13 and 14:
1999 Fd. 1" iron pipe in monument box 2.5' S. of center-line US-31 and in centerline of Haze Road to South. The Benzie County Peer Group accepted the 1" iron pipe in monument box as being the best evidence of a locally accepted corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-5: 1/4 Corner Common to Sections 11, 12, 13 and 14:
1" iron pipe replaced with 3/4" i. d. galvanized 36" long iron pipe with a stamped brass cap in a monument box 2.5'S. of centerline US-31 and in center-line of Haze Road to the South.

Witnesses:
S33°E 100.90' Fd. Nail and MDOT washer NE Face 24" Maple
S20°E 104.60' Fd. Nail and MDOT washer SW Face 26" Maple
N26°W 104.60' Center of NE bolt for steel sign post
N37°E 104.44' Center of SW bolt for steel light pole on concrete pedestal

Ratified by Peer Group
In accordance with P.A. 345
Chairman [Signature]
Date 11/9/1999



Signed by [Signature]
Surveyor's Michigan License No. 11192

Date Dec 17, 1999