

MAR 11 9 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE LIBER 2 PAGE 263
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Benzie</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 26N R 14W	L-5(Homestead)
—	T R	_____
—	T R	_____
—	T R	_____
2. Property Controlling in Section	S T R	_____
—	S T R	_____
3. Miscellaneous Property in Sec.	S T R	_____
—	S T R	_____

STATE OF MICHIGAN
BENZIE COUNTY
RECORDED

5 JAN 2000 3:27:18 PM
MICHELLE R. GRAY
REGISTER OF DEEDS
PAGES ONE

Register of Deeds Stamp & File
Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, David T. Rowe, in a field survey on October 21, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5		4		3		2			1
3													
4	7			8		9		10		11			12
5													
6	18			17		16		15		14			13
7													
8	19			20		21		22		23			24
9													
10	30			29		28		27		26			25
11													
12	31			32		33		34		35			36
13													

A. Description of original monument and accessories and/or subsequent restoration:

L-5: ¼ Corner Common to Sections 12 and 13:

G.L.O. Notes: 1839 Set ¼" Sect. Post. 10" Sugar N36°E 23lks., 12" Beech S55°W 23lks.

County Records: 1944 G. Shadko, No marker found. Set marker at a point on line midway between section corners.

1972 H. Bruning, Fd. Monument with brass cap. Concrete monument South 88.0', 12" Maple N37°E 54.72', 12" Maple N54°W 58.14

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-5: ¼ Corner Common to Sections 12 and 13:

1999 Fd. Michigan Conservation Department monument in monument box 12.5'N. of center-line US-31. The Benzie County Peer Group accepted the DNR monument as being the best evidence of a locally accepted corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-5: ¼ Corner Common to Sections 12 and 13:


Michigan Conservation Department monument replaced with ¾" i. d. galvanized 36" long iron pipe with a stamped brass cap in monument box 12.5'N. of center-line US-31.

Witnesses:

- N45°W 57.95' Fd. Spike NE Face Blazed 18" Maple
- N08°W 48.77' Fd. Nail and MDOT washer W. Face 12" Maple
- N40°E 64.64' Set nail NW Face 16" Maple
- S30°W 72.20' Set nail SE Face Triple 14" Locust, 5' above ground
- South 87.9' Fd. D.N.R. monument

Ratified by Peer Group
In accordance with P.A. 345
Chairman [Signature]

Date 11/9/1999



Signed by David T. Rowe

Date Dec 17, 1999

Surveyor's Michigan License No. 11192