

SURVEY & REMONUMENTATION

MAY 05 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 2 PAGE 53
 STATE OF MICHIGAN
 BENZIE COUNTY
 RECORDED

1/22/1997 1:55:28 PM
 MICHELLE R. GRAY
 REGISTER OF DEEDS
 # PAGES 1

Register of Deeds Stamp & File Number

For corners in

Benzie

(County)

Located In:

Corner Code #

- | | |
|------------------------------------|--|
| 1. Public Land Survey | T 26N R 35 ^{14W} M-6 |
| | T R |
| | T R |
| | T R |
| 2. Property Controlling in Section | S T R |
| | S T R |
| 3. Miscellaneous Property in Sec. | S T R |
| | S T R |

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, **John B. Smendzuik**, in a field survey on 4/11 and 6/26, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-6: G.L.O. set post and witnesses - 14" Sugar S46°W 25.08' and 12" Sugar N31°W 13.86'. Record of Surveys, Page 89, shows work done in Section 18 in July of 1868. G.A. Shadko, Michigan Department of Conservation, in June of 1944, found an iron pin and set DNR monument. Subsequent surveys of record and by Harold Bruning note D.N.R. monument at corner. Act 74 by Harold R. Bruning recorded in Liber 1, Page 129, shows he found M.S.C.D. monument.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-6: Found D.N.R. brass cap on concrete monument at corner.

Ratified by Peer Group
 In accordance with P.A. 345
 Chairman [Signature]
 Date 12/27/95

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-6: Removed D.N.R. monument remains, after Road Commission work to rebuild County Road 669 and set a 3" diameter Benzie County Remonumentation Program concrete monument in monument box.

- | | |
|-------------------------------------|------------------------------|
| Twin 6" and 8" R. Pine N22°E 95.97' | 5/8 x 24" rebar N49°W 39.85' |
| 11" R. Pine N67°E 83.97' | 5/8 x 24" rebar S49°E 56.84' |
| Power pole S35°E 57.53' | |

Signed by [Signature] Date 1/21/97
 Surveyor's Michigan License No. 30895